



1. FLASH II: Seeding schemes.
2. Parameters.
3. Tunnel Layout.
4. Time schedule.


Bart Faatz

FLASH II

Hamburg, January 27, 2011

Collaboration with PSI and SINAP (Shanghai)

# What is FLASH II.



A major extension of FLASH


2<sup>nd</sup>, variable gap, variable polarization undulator in a separate tunnel

>5 more experimental stations in a new experimental hall

next generation FEL: seeding

# Upgrade: layout after upgrade FLASH II.

- Separation FLASH and FLASH II behind last accelerator module
- Tunability of FLASH II by undulator gap change
- Extend user capacity with SASE and HHG seeding
- Use of existing infrastructure up to last accelerating module



# FLASH II: foreseen operation modes.

**Self Amplified Spontaneous Emission (SASE)** mode: Start from fluctuation in electron density spiky, but at full rep.rate and short and long pulses possible.

## **SEEDING SCHEME PHASE 1:**

**High Harmonic Generation (HHG)** mode (see also sFLASH):

*Amplify an external, frequency multiplied seed laser.*

Only short pulses, but close to single mode down to ~10 nm.

---

## **Study for seeding towards shorter wavelength:**

**High Gain Harmonic Generation (HG HG)** mode:

*Amplify a long wavelength seed and apply frequency multiplication in FEL process.*



Only short pulses (up to ~5-30 fs), but close to single mode down to ~4 nm.

**Echo Enabled Harmonic Generation (EEHG)**

Hybrid mode: HG HG with HHG source

# S2E simulation of HGHG: 32.harm of 240 nm Seed

~4 fs FWHM pulse length at 7.5 nm



# FLASH II: parameters.


<b>Beam parameters</b>	
Beam Energy	0.5 – 1.25 GeV
Normalized emittance (proj.)	1.4 mm mrad
Energy spread	0.5 MeV
Peak Current	2.5 kA
Bunches per second	<8000***
<b>Undulator parameters</b>	
Period	31.4 mm
Segments length	2.5 m
Number of segments	<=12
Focusing Structure	F0D0
<b>Radiation</b>	
Wavelength range SASE*	4-60 nm
Wavelength range HHG*	10-40 nm

\*At fundamental wavelength


\*\*\*depending on FLASH I up to 800 bunches with 1  $\mu$ s separation at 10 Hz

# Wavelengths requested for this user period and delivered the previous

Started September 2010




0.7 GeV  
1.0 GeV  
1.25 GeV



0.7 GeV  
1.0 GeV

# Wavelength range for main energies by varyang the undulator gap



Energy (GeV)	31.4 mm
0.7	10 - 40
1.0	6 - 20
1.25	4 - 13.5


NOTE: proposal for FLASH I upgrade is 23 mm period!!!!

Definitive undulator period to be decided soon

10-40 nm at 0.7 GeV with HHG seeding  
>40 nm with energies below 0.7 GeV




# Divergence for different wavelengths.



Acceptance ( $6\sigma$ ) by differential pumping stations and mirrors is around  $100 \mu\text{rad}$  (limited by far-field in the Hall: in tunnel  $\sim 140 \mu\text{rad}$  for 80 nm).


Divergence for all wavelengths depends on beam energy and (slightly) on beam emittance

# First simulations for variable polarization with an APPLE III at the 2<sup>nd</sup> harmonic (~2 nm)



Offers **limited** tunability at the 2<sup>nd</sup> harmonic with variable polarization with around ~1% of power compared to the fundamental.

# Mirror Geometry and material optimized for 2<sup>nd</sup>, 3<sup>rd</sup> and 5<sup>th</sup> harm.




Mirror geometry changed

- 1 mirror at 2 degree angle (abandoned!)
- 2 mirrors at 1 degree to create offset (see LCLS)

Consequence is changed e-beam angle and a re-iteration of the separation of FLASH II from FLASH I


At 2 degree angle




Material (not yet finalized):

- Down to 5 nm Carbon
- From 2 to 5 nm Nickel
- Below 2 nm again Carbon

# Preliminary Hall layout.




## FLASH I Hall




## FLASH II Hall

Most beamlines down to 2 nm  
at 2 degr. angle


# Tunnel Layout



# Tunnel Layout




# Tunnel Layout: space for future 3<sup>rd</sup> undulator line





FLASH III: future extension

# Technical drawings with first components





# Experimental Hall with space for additional stations



# Study of local conditions for FLASH II tunnel



# Time plan

Starting NOW 2011:

Removal of Bldg. 47A

Removal of cables along FLASH I

Sept. 2011:

Start of tunnel construction+ foundation of Experimental Hall

Needs ~3 months interruption of FLASH operation

April-May 2012:

start with technical infrastructure FLASH II tunnel

Summer 2012:

start hardware in tunnel

Winter 2013:

Vacuum connection with FLASH I


Spring 2013:

Start commissioning of FLASH II with beam and seeding

Spring 2014(?):

Start of user operation FLASH II

Experimental Hall will be shifted compared to the tunnel by several months



Thank you